REPRODUCED AT THE NATIONAL ARCHIVES

INCLO. NO. 43
SPECIAL CASES 190
NAVAJO
NEZ PERCE

Estimate for Improvement on Little Colorado River, three miles above Ganado, Arizona.

Improvements consist of a Dam across the stream, the dam can be built on a solid rock foundation, a ditch 8 miles long to a large natural Lake, and a ditch two miles and one-half long down the Valley of the Little Colorado River. Both ditches can be used for irrigation.

The valley being ½ of a mile wide all the valley available can be put to good use.

A plan for this work was furnished by me and marked No 2.

Estimate

All lumber used is to be furnished by the Fort mill.

Material: 24600 feet 2 in fine lumber

1600 feet 3 x 6 in rough fine lumber for covering dam and building flumes

600 lbs 16d nails	$ 24.00
200 lbs 8d nails	8.00

Labor

Skilled labor of one carpenter and helper 33 days at $150.00 per month for two men	$165.00
Lab. eight teams and drivers ten days at $4.00 per day per team	$320.00
Cutting ditch one and one eighth miles to reservoir, Four teams six days at $4.00 per day	$96.00
Scraping and deepening reservoir to depth of 8 feet and building embankment, 12 men at $1.50 per day for 20 days	$360.00
Amount carried forward	973.00

CV-6417-201 NN008770

NAL ARCHIVES

Amount brought forward	$973.00
Labor, 4 teams 12 days at $4.00 per day	$192.00
Labor taking out 2¼ miles of ditch	195.00
Total Labor and Material	$1360.00

Respectfully submitted,

John M. Stolenburg.